

**BILL OF QUANTITIES FOR INTERIOR WORKS OF CLASS ROOM & OTHERS** Proposal  
for M/S N. U. S. R. L, Ranchi rates inclusive material & labour charges for one classroom:

| <b>S. N</b> | <b>DESCRIPTION</b>   | <b>BRAND</b> | <b>QNTY.</b> | <b>RATE</b> | <b>AMOUNT</b> |
|-------------|--|--------------|--------------|-------------|---------------|
| <b>A.</b>   | <b>ACOUSTIC CEILING:</b>   |              |              |             |               |
|             | The false ceiling should be of gypsum tiles (gypsum pixel square edge tiles size of 595 x 12 mm pixel of 3 mm x 0.3 mm square edge with a density of 800 kg / M3)with acoustic effect, painting and finishing the roof with approved brands of putty, primer and Paint.  |              |              |             |               |
| <b>B.</b>   | <b>ACOUSTIC FABRIC CORD WALL PANELING:</b>   |              |              |             |               |
|             | The acoustic wall paneling should be done with strand soak plane board which should be of water proof, termite proof and fire resistant with a size of 600 x 1200 x 15mm.<br>The fabric used to cover the brand should be fire-resistant of good quality, the colour be used shall be decided by the authority on the basis of sample. |              |              |             |               |
| <b>C.</b>   | <b>ELECTRICAL WORKS:</b>   |              |              |             |               |
|             | Rearranging & fixing the electrical wiring for lights, fans and other utilities i.e., CCTV Cameras, sensors, A/c points, switches & sockets should be shifted from wall to wall panel.   |              |              |             |               |
|             | <b>Total:</b>  |              |              |             |               |

**APPROVED MAKES OF MATERIALS:**

|    |                      |                           |
|----|----------------------|---------------------------|
| 1. | GYPSUM BOARD         | ANUTONE / GYPSUM INDIA    |
| 2. | CHANNELS             | GYPSUM INDIA / LAFARGE    |
| 3. | STUDDS               | GYPSUM INDIA / LAFARGE    |
| 4. | POP                  | SILIGURI , MAHARAJA       |
| 5. | PLASTIC/ENAMEL PAINT | ASIAN, NEROLAC, ICI DULUX |
| 6. | WIRE/SWITCHES/LIGHTS | HAVELLS (CRABTREE)        |
| 7. | ALLUMINIUM SECTION   | HINDALCO / JINDAL         |

**TERMS & CONDITIONS:**

1. The classroom interior work should be on complete turnkey basis with acoustic wall paneling and false ceiling, which should be of 100% soundproof quality.
2. All the items should have a minimum guarantee of 10 years.
3. The university provides free electricity & water supply at the site.
4. Goods and Service Tax, educational cess or any other tax should be inclusive of the quoted price.
5. To meet the schedule of the given days for completion of work, night hours also be permitted on request.
6. Above rates are inclusive of material cost, labour cost, transport cost and Tax on unit rate basis on actual measurement at site .
7. Payment should be as per govt. norms..